

TENTATIVE DRILL DATE: Week of 3 week lead-time

United Drilling has been contracted to drill the elevator hole(s) for your project. The following information will be of assistance to you in preparation for our mobilization.

PIT:

- Construct four (4) pit walls and the pit is to be clean of oil and debris.
- Pit floor must be poured with a 30" by 30" square boxed out in the floor. A 48" by 48" block out is required for all holes over 20" in diameter. (The proper location of the square is indicated on the hoistway prints provided by the Elevator Company.)
- If work is being performed in a multi-car hatch, screening must be provided between the cars

SHAFT:

- Construct shaft walls to roof level/last elevator stop. If shaft is going to be constructed of sheetrock, we do not recommend the installation of the sheetrock prior to mobilization.
- Allow for a standard doorway (2' 5" W x 6'8" H) to enter the shaftway.
- Any protection of the shaft walls, if required, to be completed by others
- **Install hoist beam at top of shaft (to support 10,000 lbs).**
 - Please note, if hoist beam is not provided, additional charges will be incurred for United Drilling, Inc. to supply and install a beam.

ACCESS TO SHAFT:

- Allow for clear and open access to the shaftway; floors must be poured to the shaftway.
- Any protection of the floors, if required, to be completed by others

SPOILS:

- Location to be provided by others, for spoil placement (ex. Dumpster or locations outside).
- In the event that water is encountered during drilling operations, a place to pump water will need to be provided by others.

PARKING:

- 70' of parking to be provided as close to the shaftway as possible.
- If parking permits are required, they are to be obtained by others.

WATER:

- Garden hose hookup within 200' of drilling area.

HOURS OF OPERATION:

- United Drilling works Monday through Thursday (4) 10 hour days or works Monday through Friday (5) 8 hour days depending upon the location of your project.

NOISE:

- Please note that drilling is very loud; the decibel level has been recorded at 132dB. Should after hours drilling be required please contact United Drilling as soon as possible.

Please note additional items may be required after site inspection, based on site-specific conditions. If you have any questions or require additional information please contact Adrienne @ 800-321-8445 ext 11.